

LOCATION MAP

SITE DATA			
	REQUIRED	PROPOSED	SITE
ZONING/USE - PRINCIPAL	R-1-20	MUO-X	BREWERY
ZONING/USE - ACCESSORY	NA NA	NA	NA
PRINCIPAL BUILDING SQUARE FOOTAGE			5000
FRONT SETBACK	100'	20'	143.8'
SIDE SETBACK	20'	15'	30'
REAR SETBACK	40'	15'	90'
BUILDING HEIGHT	35'	35'	28
BLDG LOT COVERAGE	35.00%	60%	6.00%
PARKING	1 PER 25SF (RESTAURANTS)	1 PER 25SF (OVERFLOW)**	13
ADA PARKING	4 PER 100	4 PER 100	2

** 1 PER 25SF PER REQUIRMENTS (TOTALING 20) MET WITH OVERFLOW PARKING WITHIN 500' OF FRONT DOOR.

TOWN OF CANANDAIGUA NOTES:

- ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE MOST RECENT STANDARDS AND SPECIFICATIONS OF THE TOWN OF CANANDAIGUA AND THE APPROPRIATE WATER/SEWER AGENCIES, UNLESS OTHERWISE NOTED.
- A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO CONFORM WITH THE LATEST NYSDEC GENERAL PERMIT AND TO THE TOWN REQUIREMENTS REGARDING MAINTENANCE AND AND CONTROL OF STORM WATER QUALITY AND QUANTITY.
- ALL SWPPP'S ARE REQUIRED TO BE REVIEWED AND APPROVED BY THE TOWN CEO AND TOWN ENGINEER. THE TOWN MS4 SWPPP ACCEPTANCE FORM IS TO BE SIGNED AND INSERTED INTO THE PROJECT SWPPP PRIOR TO CONSTRUCTION.
- The owner is responsible for implementing the required swppp, including films of the "notice of intent" (noi). A copy of the NYSDEC ACKNOWLEDGEMENT LETTER is to be provided to the town development office and town engineer prior to construction.
- A COPY OF THE PROJECT SWPPP IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE, TOWN ENGINEER, AND A COPY IS TO REMAIN ONSITE DURING CONSTRUCTION AT ALL TIMES IN A MARKED AND ACCESSIBLE LOCATION.
- ANY MODIFICATIONS OR DEVIATIONS FROM THE APPROVED PLANS, CONSTRUCTION SEQUENCE, AND/OR SWPPP, INCLUDING IMPLEMENTATION OF EROSION CONTROL MEASURES AND STORM WATER MANAGEMENT AREAS, SHALL BE APPROVED BY THE TOWN OF CANANDAIGUA AND DOCUMENTED MITHIN THE PROJECT SWPPP.
- THE OWNER IS REQUIRED TO PROVIDE DAILY ONSITE OBSERVATION BY A LICENSE PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN EROSION AND SEDMENT CONTROL (CRESC). ALL SWPPP INSPECTIONS ARE TO BE IN A FORM ACCEPTABLE BY THE TOWN OF CANANDAGUA AND FORWARDED TO OWNER, THE TOWN CEO, TOWN ENGINEER, AND A COPY PLACED WITHIN THE ONSITE PROJECT SWPPP.
- THE OWNER IS RESPONSIBLE FOR PROVIDING ONSITE SWPPP INSPECTIONS BY A LICENSE PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN REGISION AND SEDIMENT CONTROL (CPESC) DURING CONSTRUCTION ONCE PER WEEK (EVERY 7 DAYS) IF UNDER 5-ACRES OF DISTURBANCE AND TWICE PER WEEK (EVERY 7 DAYS) IF 5-ACRES OR MORE WITH RECEIPT OF A 5-ACRE WATER FROM THE TOWN OF
- DEVELOPMENT IN THE CANANDAIGUA LAKE WATERSHED DISTURBING MORE THAN 5-AGRES AT ONE TIME, IS REQUIRED TO COORDINATE THE REQULAR SWPPP OBSERVATIONS REQUIRED BY THE LATEST GENERAL PERMIT WITH THE CANANDAIGUA LAKE WATERSHED INSPECTOR, THE WATERSHED PROGRAM MANAGER AND THE TOWN CODE ENFORCEMENT OFFICER.
- CONSTRUCTION SEQUENCE ALL PLANS ARE TO BE PROVIDED WITH A DETAILED CONSTRUCTION SEQUENCE. THE CONTRACTOR SHALL COMPLETE CONSTRUCTION AND INSTALL REPOSION CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED CONSTRUCTION SEQUENCE UNLESS SPECIFED OTHERMISE ON THE APPROVED DESIGN PLANS OR AT THE PRE—CONSTRUCTION MEETING.
- 11. DUST SHALL BE CONTROLLED DURING CONSTRUCTION BY THE CONTRACTOR TO MINIMIZE EFFECT ON THE ADJACENT PROPERTIES. THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL MEASURES AS NEEDED AND/OR AS DIRECTED BY THE TOWN OF CANANDAIG
- 12. THE OWNER'S CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT, MAINTENANCE, CLEANING, REPAIR AND REPLACEMENT OF EROSION CONTROL MEASURES DURING SITE CONSTRUCTION AND UNIT. THE STIE IS FULLY STRABILIZED, INSPECTED BY THE TOWN OF CANANDAIGUA, AND ISSUANCE OF THE NOTICE OF TERMINATION (NOT) HAS BEEN PROVIDED TO NYSSUANCE OF THE NOTICE OF
- . ROOF LEADERS SHOULD BE CONNECTED TO STORM SEWERS WHERE POSSIBLE, UNLESS OTHERWISE SPECIFIED ON THE APPROVED PLANS AND WITHIN THE PROJECT SWPPP.
- 15. NO SITE PREPARATION SHALL COMMENCE UNTIL A VISUAL INSPECTION BY THE TOWN OF CANANDAIGUA, CONFIRMS THE INSTALLATION OF PERIMETER SEDIMENT CONTROLS AND THE STABILIZED CONSTRUCTION ENTRANCE.
- UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF VEGETATION, THE STORM WATER MANAGEMENT FACILITIES SHALL BE CLEANED OF ACCUMULATED SILT.

LEGEND

PLANNING BOARD CHAIRMAN TOWN ENGINEER

HIGHWAY SUPERINTENDENT

PROPOSED ----- E/T

Utility Lines
R.O.W. line

Centerline Drainage

Fence Line

DATE

DATE

DATE

- THE CONSTRUCTION SITE IS NOT WITHIN 100' OF A WETLAND AS DELINEATED BY NYS DEC. THERE ARE NOT NYS DEC DELINEATED OR APPARENT WETLANDS ON THE PROPERTY AS SHOWN.
- THE CONSTRUCTION SITE IS NOT WITHIN A 100 YEAR FLOODPLAIN AS DELINEATED BY FEMA. Contour Line
 - WATER & SEWER: TOWN OF CANANDAIGUA WATER & CANANDAIGUA LAKE COUNTY SEWER DISTRICT
 - TOPOGRAPHIC SURVEY OF THE SITE WAS PROVIDED BY MARKS ENGINEERING. P.C. ON 01/25/2018.

MAP OF SURVEY PREPARED FOR SARAH-FRANK, LLC BY YEARS BOUNDARY DATED DECEMBER 28, 2017 BEING FILE NO. YB5691.

GENERAL NOTES:

- ENERAL NOISS:

 THE CONTRACTOR SHALL MAINTAIN ALL UTILITIES AND PROPERTY MARKERS, IT IS THE NYS LAW TO CALL NYS DIG SAFE FOR UFPO (811) PRIOR TO ANY EXCAVATION.

 THE ROADWAY SHALL BE KEPT FREE OF DEBRIS DURING CONSTRUCTION.
 THE CONTRACTOR IS RESPONSIBLE FOR SAFETY CONTROL DEVICES. SUCH DEVICES (BAARICADES, FENCING, ETC.) SHALL BE IMPLEMENTED TO MINIMIZE RISK OF INJURY TO PEDESTRIANS AND WORKERS. CONSTRUCTION ACTIVITY SHALL BE CONDUCTED WITHIN COMPLIANCE WITH OSHA GUIDELINES.
- CUMPLIANCE. WITH OSHA GUIDELINES.

 4. PLANS ARE GRAPHIC REPRESENTATIONS OF WORK TO BE PERFORMED. THESE PLANS ARE TO INTENDED TO CONVEY ENGINEERING INFORMATION ONLY.

 5. CONTRACTOR TO VERIFY ALL PROPERTY LINES, LOCATIONS, GRADES AND INVERTS AND NOTIFY VISINEER OF ANY DISCREPANCIES PRIOR TO THE START OF WORK.

 6. ALL SPECIFIED MATERIALS ARE TO BE INSTALLED AS PER MANUFACTURES RECOMMENDATIONS OR INDUSTRY STANDARD.
- ENGINEERING, P.C. ON 01/25/2018.

 6. ELEVATIONS ARE BASED ON NAVD 88 DATUM.

 SYSTEM IS BASED ON NAD 83 DATUM.

 MAP REFERENCES:

 A MAD OF SUBJECT DEPOLATED FOR SABAH-FRANK LIC BY YEARS

 RECOMMENDATIONS OR DEVIATIONS FROM THE APPROVED PLANS, NYS BUILDING CODES, AND/OR LOCAL REGULATIONS FROM THE APPROVED PLANS, NYS BUILDING CODES, AND/OR LOCAL REGULATIONS FROM THE APPROVED PLANS, NYS BUILDING CODES, AND/OR LOCAL REGULATIONS FROM THE APPROVED PLANS, NYS BUILDING CODES, AND/OR LOCAL REGULATIONS OR GOVERNING AUTHORITIES WILL BE DONE AT THE RISK OF THE CLIENT.

 8. ALL CONSTRUCTION SHALL COMPLY WITH CURRENT NYS AND LOCAL BUILDING CODES AS WELL AS NATIONAL ELECTRIC CODE.

CONSTRUCTION SEQUENCE:

- INSTALL TEMPORARY EROSION CONTROL MEASURES INCLUDING BUT NOT LIMITED TO: SILT FENCE, STABILIZED ENTRANCES, ETC. THE CONTRACTOR SHALL SELECTIVELY REMOVE VEGETATION AND ROOTS AS REQUIRED.
- 3. PLACE SILT FENCE FOR STOCKPILE AREA STRIP TOPSOIL
- CONSTRUCT BUILDING AND INSTALL UTILITIES MAINTAIN EROSION CONTROL PRACTICES AS NECESSARY. IF ADDITIONAL MEASURE ARE REQUIRED THESE SHALL BE PROVIDED AT THE EXPENSE OF THE OWNER OR CONTRACTOR.
- 7. IN THE EVENT THERE IS A SEDIMENT DISCHARGE OR FAILURE THE CONTRACTOR OR OWNER SHALL BE RESPONSIBLE FOR RESTORATION.
- FINAL GRADE SEED AND MULCH DISTURBED AREAS AS SOON AS POSSIBLE. INSTALL DRY SWALE AFTER AREAS CONTRIBUTING DRAINAGE ARE STABILIZED.
- D. REMOVE TEMPORARY EROSION CONTROLS AFTER AREAS ARE STABILIZED WITH VEGETATION, STONE OR ASPHALT.
- . NO PHOSPHOROUS SHALL BE USED FOR FERTILIZER, SOIL AUGMENTATION, ETC. UNLESS SOIL TESTS BY A HORTICULIVAL LABORATORY SPECIFICALLY INDICATE REQUIREMENTS FOR PLANT GROWTH. IF PHOSPHORUS IS REQUIRED IT SHALL BE APPLIED AT THE MINIMUM.

PHOSPHORUS NOTES:





3365 EAST LAKE RD TOWN OF CANANDAIG

SITE PLAN

DRAWN BY BAM BAM CHECKED BY: AS NOTED SCALE 16-073 IOB NO.: 02/09/2018 DATE: TAX MAP#: 98.11-2-8.000

C100

