## ONE STAGE(PRELIMINARY/FINAL) SITE PLAN SET FOR

# SINGLE FAMILY HOME CONSTRUCTION 5285 BLACK POINT DRIVE

## TOWN OF CANANDAIGUA ONTARIO COUNTY -- STATE OF NEW YORK





AERIAL LOCUS NOT TO SCALE

### ONE STAGE SITE PLAN APPROVAL


PLANNING BOARD CHAIRPERSON	DATE
TOWN HIGHWAY & WATER SUPERINTENDENT	DATF
	27
TOWN FNGINFFR	DATE
TOWN LINGINLLIX	DAIL

NO BUILDING PERMIT MAY BE ISSUED UNTIL FINAL SITE PLAN APPROVAL HAS BEEN GRANTED AND THE FINAL SITE PLAN SIGNED BY THE PLANNING BOARD CHAIRPERSON.

FOR PERMITTING ONLY



STATE EDUCATION LAW IT IS A VIOLATION FOR ANY PERSON TO ALTER ANY DOCUMENT THAT BEARS THE SEAL OF A PROFESSIONAL ENGINEER, UNLESS THE PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. IF A DOCUMENT BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE DOCUMENT THEIR SEAL SIGNATURE AND THE DATE OF SUCH ALTERATION, AND  $\ensuremath{\mathsf{A}}$ SPECIFIC DESCRIPTION OF THE ALTERATION.



Site Plan Drawings Prepared For:

Marie W. McNabb & Ernest C. Whitbeck IV

5285 Black Point Drive Town of Canandaigua County of Ontario

State of New York

File# 17016 Scale AS NOTED T.m. # 154.04-1-7.0 Date: 10/03/2022 **C-0** 


SHEET INDEX:


EXISTING CONDITIONS PLAN


**COVER SHEET** 

SITE DETAILS


SITE PLAN







### 4' DIAMETER PRECAST CONCRETE DRY WELL DETAIL



#### TEMPORARY SEDIMENT BASIN DETAIL NOT TO SCALE



- ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE MOST RECENT STANDARDS AND SPECIFICATIONS OF THE TOWN OF CANANDAIGUA AND THE APPROPRIATE WATER /
- SEWER AGENCIES, UNLESS OTHERWISE NOTED. 2. A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO CONFORM WITH THE LATEST NYSDEC GENERAL PERMIT AND TO THE TOWN REQUIREMENTS REGARDING
- MAINTENANCE AND CONTROL OF STORMWATER QUALITY AND QUANTITY. ALL SWPPP'S ARE REQUIRED TO BE REVIEWED AND APPROVED BY THE TOWN CEO AND TOWN ENGINEER. THE TOWN MS4 SWPPP ACCEPTANCE FORM IS TO BE SIGNED AND
- INSERTED INTO THE PROJECT SWPPP PRIOR TO CONSTRUCTION.
- 4. THE OWNER IS RESPONSIBLE FOR IMPLEMENTING THE REQUIRED SWPPP, INCLUDING FILING OF THE "NOTICE OF INTENT" (NOI). A COPY OF THE NYSDEC ACKNOWLEDGEMENT LETTER
- IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE AND TOWN ENGINEER PRIOR TO CONSTRUCTION. A COPY OF THE PROJECT SWPPP IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE, TOWN ENGINEER AND A COPY IS TO REMAIN ON SITE DURING CONSTRUCTION AT ALL
- TIMES IN A MARKED AND ACCESSIBLE LOCATION. 6. ANY MODIFICATIONS OR DEVIATIONS FROM THE APPROVED PLANS, CONSTRUCTION SEQUENCE, AND/OR SWPPP INCLUDING IMPLEMENTATION OF EROSION CONTROL MEASURES AND STORMWATER MANAGEMENT AREAS SHALL BE APPROVED BY THE TOWN OF CANANDAIGUA AND DOCUMENTED WITHIN THE PROJECT SWPPP
- 7. THE OWNER IS REQUIRED TO PROVIDE DAILY ON-SITE OBSERVATION BY A LICENSED PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC). ALL SWPPP INSPECTIONS ARE TO BE IN A FORM ACCEPTABLE BY THE TOWN OF CANANDAIGUA AND FORWARDED TO THE OWNER, THE TOWN CEO, TOWN ENGINEER, AND A COPY
- PLACED WITHIN THE ON-SITE PROJECT SWPPP 8. THE OWNER IS RESPONSIBLE FOR PROVIDING ON-SITE SWPPP INSPECTIONS BY A LICENSED PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC) DURING CONSTRUCTION ONCE PER WEEK (EVERY 7 DAYS) IF UNDER 5 ACRES OF DISTURBANCE AND TWICE PER WEEK (EVERY 7 DAYS) IF 5 ACRES OR MORE WITH
- RECEIPT OF A 5-ACRE WAIVER FROM THE TOWN OF CANANDAIGUA (MS4). 9. DEVELOPMENT IN THE CANANDAIGUA LAKE WATERSHED DISTURBING MORE THAN 5 ACRES AT ONE TIME IS REQUIRED TO COORDINATE THE REGULAR SWPPP OBSERVATIONS
- REQUIRED BY THE LATEST GENERAL PERMIT WITH THE CANANDAIGUA LAKE WATERSHED INSPECTOR, THE WATERSHED PROGRAM MANAGER, AND THE TOWN CODE ENFORCEMENT 10. CONSTRUCTION SEQUENCE: ALL PLANS ARE TO BE PROVIDED WITH A DETAILED CONSTRUCTION SEQUENCE. THE CONTRACTOR SHALL COMPLETE CONSTRUCTION AND INSTALL
- EROSION CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED CONSTRUCTION SEQUENCE UNLESS SPECIFIED OTHERWISE ON THE APPROVED DESIGN PLANS OR AT THE 11. DUST SHALL CONTROL DURING CONSTRUCTION BY THE CONTRACTOR TO MINIMIZE EFFECT ON THE ADJACENT PROPERTIES. THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL
- MEASURES AS NEEDED AND/OR AS DIRECTED BY THE TOWN OF CANANDAIGUA. 12. THE OWNERS CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT, MAINTENANCE, CLEANING, REPAIR, AND REPLACEMENT OF EROSION CONTROL MEASURES DURING SITE CONSTRUCTION AND UNTIL THE SITE IS FULLY STABILIZED, INSPECTED BY THE TOWN OF CANANDAIGUA, AND ISSUANCE OF THE NOTICE OF TERMINATION (NOT) HAS BEEN
- PROVIDED TO NYSDEC. 13. ROOF LEADERS SHOULD BE CONNECTED TO STORM SEWERS WHERE POSSIBLE UNLESS OTHERWISE SPECIFIED ON THE APPROVED PLANS AND WITHIN THE PROJECT SWPPP. 14. NO SITE PREPARATION SHALL COMMENCE UNTIL A VISUAL INSPECTION BY THE TOWN OF CANANDAIGUA CONFIRMS THE INSTALLATION OF PERIMETER SEDIMENT CONTROLS AND THE
- 15. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF VEGETATION, THE STORMWATER MANAGEMENT FACILITY SHALL BE CLEANED OF ACCUMULATED SILT. 16. ALL SITE STABILIZATION IS TO BE IN ACCORDANCE WITH THE LATEST VERSIONS OF THE NYSDEC STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL AND THE
- NYSDEC GENERAL PERMIT REQUIREMENTS (WHERE APPLICABLE). WHERE SOIL DISTURBANCE ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, SOIL STABILIZATION MEASURES SHALL BE INITIATED BY THE END OF THE NEXT BUSINESS DAY AND COMPLETED WITHIN 14 DAYS (7 DAYS IF OVER 5-ACRES OF DISTURBANCE, OR 3 DAYS IF BETWEEN
- 17. ADDITIONAL TEMPORARY AND PERMANENT SEEDING AND SITE STABILIZATION REQUIREMENTS: A. ALL DISTURBED AREAS INCLUDING TOPSOIL STOCKPILES AND STORMWATER MANAGEMENT FACILITIES ARE TO BE STABILIZED WITHIN SEVEN (7) DAYS AFTER COMPLETION.
- WHERE SOIL DISTURBANCE ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, SOIL STABILIZATION MEASURES SHALL BE INITIATED BY THE END OF THE NEXT BUSINESS DAY AND COMPLETED WITHIN 14 DAYS (7 DAYS IF OVER 5-ACRES OF DISTURBANCE, OR 3 DAYS IF BETWEEN NOVEMBER 15TH AND APRIL 1ST). TEMPORARY SEEDING OF DISTURBED AREAS SHALL BE PROVIDED AS FOLLOWS:
- THE SURFACE TWO INCHES OF SOIL SHOULD BE LOOSENED BY DISKING RAKING OR BACK-BLADING WITH A BULLDOZER
   FERTILIZE WITH 300 LBS PER ACRE OR 7 LBS PER 1000 SQUARE FEET
   NO PHOSPHORUS SHALL BE USED UNLESS SOIL TESTING HAS BEEN COMPLETED AND TESTED BY HORTICULTURE TESTING LAB AND THE SOIL TESTS SPECIFICALLY
- INDICATE A PHOSPHORUS DEFICIENCY THAT IS HARMFUL OR WILL PREVENT NEW LAWNS AND PLANTINGS FROM ESTABLISHING PROPERLY. IF SOIL TESTS INDICATE A PHOSPHORUS DEFICIENCY THAT WILL IMPACT PLANT AND LAWN ESTABLISHMENT, PHOSPHORUS SHALL BE APPLIED AT THE MINIMUM RECOMMENDED LEVEL PRESCRIBED IN THE SOIL TEST FOLLOWING ALL NYSDEC REGULATIONS.

SPRING/SUMMER/EARLY FALL	LBS/ACRE	LBS/1,000 SQ. ACRE
ANNUAL RYE GRASS	30	0.7
PERENNIAL RYEGRASS	30	0.7

THE FOLLOWING SEED MIX SHALL BE USED:

- CEREAL RYE
- SEED SHOULD HAVE A GERMINATION RATE OF AT LEAST 85% AND MINIMAL INERT MATERIAL. C. DISTURBED AREAS SHALL BE STABILIZED USING PERMANENT LAWN SEED MIX UPON COMPLETION OF GRADING AND CONSTRUCTION:

LBS/ACRE LBS/1,000 SQ. ACRE BIRDSFOOT TREFOIL OR COMMON WHITE CLOVER 8 OR 8 0.20 OR 0.20 TALL FESCUE 2 OR 5 0.05 OR 0.10 REDTOP OR RYEGRASS (PERENNIAL)

- SEEDING RATE 6 LBS PER 1000 SQUARE FEET . MULCH: STRAW OR WOOD FIBER MULCH USED WITH HYDROSEEDING METHOD AT 2 TONS PER ACRE WITH TACKIFIER.
- FOR FALL OR EARLY WINTER, SEED WITH CERTIFIED "AROOSTOCK" WINTER RYE (CEREAL RYE) AT 100 LBS PER ACRE.
- PERMANENT STABILIZATION FOR STEEP SLOPES GREATER THAN 3:1 SHALL INCLUDE JUTE MESH BLANKET AND CROWN VETCH SEED WITH PERENNIAL RYEGRASS.

   NO PHOSPHORUS SHALL BE USED UNLESS SOIL TESTING HAS BEEN COMPLETED AND TESTED BY HORTICULTURE TESTING LAB AND THE SOIL TESTS SPECIFICALLY. INDICATE A PHOSPHORUS DEFICIENCY THAT IS HARMFUL OR WILL PREVENT NEW LAWNS AND PLANTINGS FROM ESTABLISHING PROPERLY IF SOIL TESTS INDICATE A PHOSPHORUS DEFICIENCY THAT WILL IMPACT PLANT AND LAWN ESTABLISHMENT, PHOSPHORUS SHALL BE APPLIED AT THE MINIMUM RECOMMENDED LEVEL PRESCRIBED IN THE SOIL TEST FOLLOWING ALL NYSDEC REGULATIONS.
- 18. THE CONTRACTOR SHALL LOCATE, MARK, SAFEGUARD, AND PRESERVE ALL SURVEY CONTROL MONUMENTS AND RIGHT-OF-WAY MONUMENTS IN THE AREAS OF CONSTRUCTION.
- 19. EXISTING UNDERGROUND UTILITIES SHOWN HEREIN WERE PLOTTED FROM FIELD LOCATIONS AND/OR UTILITY COMPANY RECORD PLANS. PRIOR TO ANY CONSTRUCTION THE CONTRACTOR SHALL CALL THE DIG SAFELY NEW YORK UFPO HOTLINE AT 1-800-962-7962 FOR STAKEOUT OF EXISTING UTILITIES. THE CONTRACTOR SHALL DETERMINE EXACT LOCATION AND ELEVATION OF UNDERGROUND UTILITIES BEFORE COMMENCING CONSTRUCTION. CONTRACTOR SHALL MAKE EXPLORATION EXCAVATIONS TO LOCATE EXISTING
- UNDERGROUND FACILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS AS REQUIRED TO MEET THE EXISTING CONDITIONS 20. THE HOMEBUILDER WILL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING INDIVIDUAL LOT EROSION AND SEDIMENT CONTROL MEASURES DURING HOUSE CONSTRUCTION. MEASURES
- TO BE MAINTAINED UNTIL FINAL LOT LAWN GRADING AND SITE IS FULLY STABILIZED AND INSPECTED BY THE TOWN OF CANANDAIGUA. 21. ANY ADDITIONAL OR EROSION OR SEDIMENT CONTROL MEASURES DEEMED NECESSARY BY THE TOWN OF CANANDAIGUA OR A REPRESENTATIVE THEREOF SHALL BE PROVIDED BY
- THE OWNER AND INSTALLED BY THE CONTRACTOR. 22. SEDIMENT CONTROL MEASURES ARE TO BE ESTABLISHED PRIOR TO COMMENCING EARTHWORK. SEDIMENT CONTROL MEASURES ARE TO BE MAINTAINED BY THE CONTRACTOR UNTIL
- UPSTREAM GROUND COVER HAS BEEN ESTABLISHED AND REMOVAL IS APPROVED BY THE TOWN OF CANANDAIGUA. 23. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING, REPLACING, AND SUBSEQUENTLY REMOVING TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES.

State of New York

- 24. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ADJOINING PROPERTIES, ROADWAYS, DRAINAGE WAYS, AND SINKS OF SILT ACCUMULATION AS NEEDED AND AS DETERMINED / REQUESTED BY THE TOWN OF CANANDAIGUA.
- 25. ANY FINAL GRADE DEVIATIONS OF HOUSE PAD ELEVATIONS MORE THAN 12 INCHES SHALL BE APPROVED BY THE PLANNING BOARD.

#### ONE STAGE SITE PLAN APPROVAL

PLANNING BOARD CHAIRPERSON	DATE
TOWN HIGHWAY & WATER SUPERINTENDENT	DATE
TOWN ENGINEER	DATE

NO BUILDING PERMIT MAY BE ISSUED UNTIL FINAL SITE PLAN APPROVAL HAS BEEN GRANTED AND THE FINAL SITE PLAN SIGNED BY THE PLANNING BOARD CHAIRPERSON.

File# 17016

Scale AS NOTED



FABRIC OR EQUAL (STAPLE TO LATHE)

RURY FND

4" MIN TOPSOIL

ON-SITE MATERIAL

LANDSCAPE AREAS)

SELECT FILL SAFETY

12"(MIN)

(12"MIN)

FROM SPOILS

(SUITABLE UNDER

SILT FENCE DETAIL

NOT TO SCALE

PAVEMENT
MINIMUM 6" BEYOND

PAYMENT LIMIT FOR

- ROCK EKCAVATION -

O.D. + 36"

12"(MIN)

NON-PAVEMENT/LAWN AREAS

— SAWCUT EXISTING

- EXISTING PAVEMENT

TYPE 2 CRUSHER RUN

LIMESTONE CONFORMING TO

TYPE 4 GRAVEL MAY BE

6" DETECTABLE TRACER

10 GUAGE COPPERHEAD

TRACER WIRE FIXED TO TOP

GRANULAR SAND CONFORMING

703-06. ADDITIONAL BEDDING

CONDITIONS MAY BE REQUIRED

TO NYSDOT SPEC. SECTION

FOR UNSTABLE TRENCH

TAPE INSTALLED PER

MANUFACTURERS

- WATER MAIN OR

STORM DRAIN PIPE

RECOMMENDATIONS

NYSDOT SPEC SECTION 703-4

(UNDER DEDICATED ROADWAYS)

UTILIZED UNDER PARKING AREAS

- TACK COAT ON EXISTING

ASPHALT SURFACE GRADE

HFMS 2H NYSDOT MATERIAL DESIGNATION SECTION 407

PAVEMENT

**/** 

VENEZIA AND ASSOCIATES 5120 LAURA LANE, CANANDAIGUA NY rocco@veneziasurvey.com

PAVEMENT AREAS


JOYCE CONSULTING GROUP, PC CONSULTING 100 WYMAN ROAD, BRAINTREE MA www.joyccg.com 781.817.6120

WATER MAIN & DRAIN

BEDDING DETAIL

NOT TO SCALE

PER SECTION 7209 OF ARTICLE 145 OF THE NEW YORK STATE EDUCATION LAW IT IS A VIOLATION FOR ANY PERSON TO ALTER ANY DOCUMENT THAT BEARS THE SEAL OF A PROFESSIONAL ENGINEER, UNLESS THE PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. IF A DOCUMENT BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE DOCUMENT THEIR SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.



Revisions			NYS Land Surveyor	
NO.	Date	Description	Ву	
				D 4 17

Drawing Title:

SITE DETAILS

Site Plan Prepared For:

Marie W. McNabb & Ernest C. Whitbeck IV

5285 Black Point Drive Town of Canandaigua County of Ontario

T.m. # 154.04-1-7.0 Date: 10/03/2022 Sheet: