

SITE DISTURBANCE NOTE

ESTIMATED SITE DISTURBANCE AREA IS APPROXIMATELY 800 SQUARE FEET

ESTIMATED SOIL VOLUME EXCAVATED IS APPROXIMATELY 25 CUBIC YARDS.

SHORELINE GUIDELINES STATEMENT

PROJECT IS IN CONFORMANCE WITH THE SHORELINE GUIDELINES AS ALL AFFECTED PLANTINGS FROM THE CONSTRUCTION PROCESS ARE TO BE TRANSPLANTED AND RE-ESTABLISHED SURROUNDING THE BUILDING ADDITION. OWNERS ARE ACTIVE GARDENERS AND WILL PROVIDE AMPLE LANDSCAPING TO BLEND WITH THE MINOR (10'L X 12.4'H) EXTENSION OF THE BUILDING STRUCTURE.

NOT FOR CONSTRUCTION

THIS PLAN HAS NOT RECEIVED FINAL APPROVAL FROM ALL REVIEWING AGENCIES. IT IS SUBJECT TO REVISIONS AND SHOULD NOT BE USED FOR CONSTRUCTION PURPOSES UNTIL THIS NOTE IS REMOVED.

DRAWING ALTERATION THE FOLLOWING IS AN EXCERPT FROM THE NEW YORK EDUCATION LAW, ARTICLE 145, SECTION 7209, AND APPLIES TO THIS DRAWING: "IT IS A VIOLATION OF THIS LAW FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED ENGINEER OR LAND SURVEYOR, TO ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ENGINEER OR LAND SURVEYOR IS ALTERED, THE ALTERING ENGINEER OR LAND SURVEYOR SHALL AFFIX TO THE ITEM, HIS SEAL AND THE NOTATION "ALTERED BY", FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.


COPYRIGHT 2020 BY PROFESSIONAL ENGINEERING SERVICES/GROUP

PHOSPHOROUS NOTES

2) IF SOIL TESTS INDICATE A PHOSPHOROUS DEFICIENCY THAT WILL IMPACT PLANT AND LAWN ESTABLISHMENT, PHOSPHOROUS SHALL BE APPLIED AT THE MINIMUM RECOMMENDED LEVEL PRESCRIBED IN THE SOIL TEST FOLLOWING ALL NYS DEC REQUIREMENTS.

1) NO PHOSPHOROUS SHALL BE USED AT PLANTING TIME UNLESS SOIL TESTING HAS BEEN COMPLETED AND TESTED BY A HORTICULTURAL TESTING LAB AND THE SOIL TESTS SPECIFICALLY INDICATE A PHOSPHOROUS DEFICIENCY THAT IS HARMFUL, OR WILL PREVENT NEW LAWNS AND PLANTINGS FROM ESTABLISHING PROPERLY.





HYDRANT/ WATER VALVE


DEEP/PERCOLATION TEST HOLE

WORK PLAN / LEGEND

- (A) INSTALL SILT FENCING PER DETAIL BACKED WITH A STRAW BALE ROW PLACED IMMEDIATELY DOWNSLOPE OF THE SILT FENCING.
- (B) ELECTRIC SERVICE UNAFFECTED BY ADDITION AND WILL REMAIN IN PLACE.
- (C) EXCAVATE AND REVEAL EXISTING SEPTIC TANK. CONFIRM AVAILABLE LAND AREA AND INVERT ELEVATIONS FOR REPLACEMENT SEPTIC TANK. REVIEW FIELD FINDINGS WITH ENGINEER AND WATERSHED INSPECTOR. REPLACE EXISTING 750 GALLON SINGLE COMPARTMENT TANK WITH 1500 GALLON DUAL COMPARTMENT POLY TANK OR THE LARGEST VOLUME TANK FEASIBLE TO FIT WITHIN AVAILABLE AREA BASED ON THE ENGINEER'S AND WATERSHED INSPECTOR'S DETERMINATION. INSTALL MICROBIAL INOCULATOR IN NEW TANK PER MANUFACTURER'S SPECIFICATIONS. NOTE ELECTRIC SERVICE IS TO BE PROVIDED TO INNOCULATOR. THIS DEVICE IS ALSO TO HAVE A VISUAL AND AUDIO ALARM INSTALLED.
- (D) EXCAVATE AND REVEAL EXISTING LEACHING CHAMBERS. REVIEW THE CONDITION AND LOCATIONS WITH ENGINEER. ADJUST LOCATIONS IF EXISTING LOCATIONS ARE FOUND TO BE TOO CLOSE TO BUILDING ADDITION FOOTINGS. REMOVE AND REPLACE LEACHING CHAMBERS AS/IF NECESSARY PER DETERMINATION BY ENGINEER AND WATERSHED INSPECTOR. CONFIRM PIPING CONDITION AND DISTRIBUTION FROM TANK TO LEACHING CHAMBERS. REPLACE PIPING AS NECESSARY. SLEEVE PIPES IN LARGER DIAMETER PIPES TO PROTECT AND FACILITATE FUTURE SERVICE AS DETERMINED BY ENGINEER.
- (E) REMOVE AFFECTED CONCRETE PATIO AREA WITHIN BUILDING ADDITION FOUNDATION. NOTE NEW PLANTER ON EAST SIDE TO CONTAIN RELOCATED PLANTINGS FROM EXISTING PLANTER BEING ELIMINATED. NEW PLANTER DIMENSIONS 1' X 15'. NOTE THAT DEBRIS FROM THE DEMOLITION ACTIVITY MUST BE HAULED TO A LANDFILL PERMITTED TO ACCEPT SUCH SOLID WASTE.
- (F) CONSTRUCT BUILDING ADDITION PER ARCHITECTURAL PLANS. FINISHED FLOOR ELEVATION TO BE MAINTAINED. RIDGE LINE OF ADDITION IS 12.4' ABOVE THE FINISHED FLOOR ELEVATION PER CURRENT ARCHITECTURAL ELEVATION DRAWINGS AS PROVIDED BY THE PROJECT ARCHITECT.
- (G) TEMPORARY MOBILIZATION AREA FOR EQUIPMENT DURING CONSTRUCTION TIME PERIOD. NOTE: VERBAL PERMISSION FROM NEIGHBOR AT 4791 WEST LAKE ROAD FOR ACCESS ALONG SOUTH PROPERTY LINE HAS BEEN GRANTED AND WILL BE FORMALIZED IN WRITING.
- (H) ESTIMATED DISTURBANCE LIMITS.

EROSION CONTROL CONSTRUCTION SEQUENCE

- 1. INSTALL EROSION CONTROL MEASURES PRIOR TO ANY EXCAVATION WORK.
- 2. INSTALL TEMPORARY SWALES TO INTERCEPT SURFACE WATER AND DIRECT IT AWAY FROM THE WORK AREA AS WORK PROCEEDS. SOON AS PRACTICABLE.
- 3. FINISH GRADE AND PROMOTE VEGETATION ON ALL EXPOSED AREAS AS AND REPAIR AS NECESSARY.
- 4. MONITOR SILT FENCING FOR SILT ACCUMULATION. REMOVE, REPLACE
- 5. REMOVE EROSION CONTROLS AND CEASE MONITORING ONLY AFTER APPROVAL HAS BEEN GRANTED BY THE TOWN OR WATERSHED INSPECTOR.
- 6. IN ADDITION TO THESE MEASURES, THE CONTRACTOR SHALL COMPLY WITH WHATEVER SUPPLEMENTARY MEASURES MAY BE REQUIRED TO ENHANCE OR IMPROVE THE CONTROL OF EROSION ON THIS SITE, AS ORDERED BY THE TOWN OR WATERSHED INSPECTOR.



SITE DATA / GENERAL NOTES

1. ZONING:

ZONE RLD

- FRONT SETBACK: 50'
- REAR (LAKE) SETBACK: 30' - SIDE SETBACK: 8'
- MAX. HEIGHT: 25'
- % COVERAGE: 25% (BUILDING) 40% (LOT)
- ELECTRIC: NYSEG OVERHEAD GAS: NYSEG
- WATER: TOWN OF CANANDAIGUA SEWER: SEPTIC
- 3. FLOOD ZONE PER FEMA FIRM PANEL 3605980025C EFFECTIVE DATE MARCH 3, 1997, A PORTION OF THIS PROJECT IS LOCATED IN FLOOD ZONE AE THAT IS IDENTIFIED AS AN AREA LOCATED WITHIN THE 100 YEAR FLOODPLAIN.
- 4. ALL DISTANCES AND ELEVATIONS ARE MEASURED IN DECIMAL FEET. ELEVATIONS SHOWN ARE ON NAVID 1983 DATUM.
- 5. BASE MAPPING FOR THIS DRAWING WAS PROVIDED BY VENEZIA LAND SURVEYORS FROM AN INSTRUMENT SURVEY COMPLETED
- 6. AREA OF LAND PARCEL = 0.168 ACRES FROM MHW TO ROW.

EROSION CONTROL NOTES

1) IF REQUIRED, THE CONTRACTOR SHALL PROVIDE ADDITIONAL TEMPORARY EROSION CONTROL MEASURES, AT THE EXPENSE OF THE CONTRACTOR OR OWNER, TO PREVENT SILTATION OF DOWNSTREAM PROPERTIES.

2) IN THE EVENT THERE IS A FAILURE OF AN EROSION CONTROL DEVICE, THE CONTRACTOR AND OWNER ARE RESPONSIBLE TO RESTORE DOWNSTREAM AREAS AT THEIR EXPENSE.

3) ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE DESIGNED, INSTALLED AND MAINTAINED PER THE REQUIREMENTS SET FORTH IN THE LATEST EDITION (2016) OF THE NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL.


APPROVALS

TOWN PLANNING BOARD CHAIRPERSON	DATE
TOWN ENGINEER	DATE
TOWN HIGWAY AND WATER SUPERINTENDENT	DATE


NO PRELIMINARY SITE PLAN REVIEW WAS REQUIRED

-, AS ONDERED DI THE TOWN ON WATERSHED INSLECTOR.				EXISTING AND PROPOSED CONDITIONS						
OF NC	REVISIONS			SITE AND UTILITY PLAN — 4789 WEST LAKE ROAD						
A HAR HAR HAR HAR HAR HAR HAR HAR HAR HA	DATE	BY		TOWN OF CANANDAIGUA, ONTARIO COUNTY, NEW YORK S						
	9/16/20 9/22/20		TOC PRC REVIEW TOWN REVIEW	PROFESSIONAL				CLIENT:		
	9/22/20		TOWN REVIEW	ENGINEERING			HAROLD & TERRI BOBRY 16 BRETTON WOODS DR			
				7171 VICTOR — PITTSFORD ROAD VICTOR, NEW YORK 14564 TEL. (585) 924—1860 EMAIL: PROENGINEER1@PRODIGY.NET					ROCHESTER, NY 14618 PHONE:(585) 748-5464	
									TAX ACCOUNT NO. 140.14-1-16.100	
or of ession dutility				— DATE: — <i>SEPT 2020</i>	ENGINEER: S.A.H	SURVEYOR: A.A. V.	SCALE: $1'' = 10'$	SHEET NO.: 1 OF 2	DRAWING NO.: 200901EX1	
				32, , 2020	<i>9.71.77</i>	,, I. V.	, , , , ,	, 3, 2	ZOOOOTEXT	


5' 10' SCALE: 1"=10'



1500 GALLON DUAL COMPARTMENT POLY SEPTIC TANK EXAMPLE



STAKED STRAW BALE DETAIL N.T.S.



NOTE: SILTATION FENCES ARE TO BE REPLACED AS NECESSARY DUE TO DAMAGE OR WHEN FILLED WITH SILT. SILT SHALL BE REMOVED FROM IN FRONT OF THE FENCES REGULARLY TO PREVENT EXCESSIVE SOIL BEARING WEIGHT ON THE FENCE.

IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE AND INITIALIZE EROSION CONTROL MEASURES. SILTATION FENCES ARE TO BE MAINTAINED TO THE SATISFACTION OF THE TOWN INSPECTION PERSONNEL AND WILL BE REMOVED BY THE CONTRACTOR ONCE GROUND COVER IS RE-ESTABLISHED.

SILT FENCE DETAIL N.T.S.

TENTATIVE CONSTRUCTION SCHEDULE/SEQUENCE

PROPOSED START DATE IS APPROXIMATELY NOVEMBER 5, 2020.

CONSTRUCTION DURATION IS ESTIMATED TO BE SIX MONTHS (WEATHER PERMITTING) FROM START DATE. STAGING AREA FOR CONSTRUCTION EQUIPMENT IS TO BE LOCATED ON COMMON DRIVEWAY AND DOWNSLOPE LAWN AREA.

CONSTRUCTION SEQUENCE IS:

- 1) MOBILIZE EQUIPMENT IN STAGING AREA.
- RECEIVE MATERIALS FOR CONSTRUCTION AND PLACE IN STAGING AREA.
- 3) PLACE EROSION CONTROLS DOWNSLOPE OF WORK AREA WHERE SHOWN ON PLANS.
- 4) PERFORM DEMOLITION WORK DEFINED IN WORK LEGEND, REMOVE ALL DEBRIS AND EXTRANEOUS MATERIALS. EXCESS SOIL TO REMOVED AND NOT STOCKPILED.
- 5) CONSTRUCT IMPROVEMENTS PROGRESSIVELY AS GENERALLY FOLLOWS: INSTALL NEW WASTEWATER SYSTEM COMPONENTS CONSTRUCT NEW ADDITION
- TOPSOIL AND SEED DISTURBED AREAS PER EROSION CONTROL NOTES.
- CLEAN SITE AND DEMOBILIZE EQUIPMENT AND MATERIALS.

SOIL STABILIZATION MEASURES NOTE:

IN AREAS WHERE SOIL DISTURBANCE ACTIVITY HAS BEEN TEMPORARILY OR PERMANENTLY CEASED, TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES SHALL BE IMPLEMENTED WITHIN SEVEN DAYS FROM THE DATE THE SOIL DISTUBANCE ACTIVITY CEASED. THE SOIL STABILIZATION MEASURES SELECTED SHALL BE IN CONFORMANCE WITH THE MOST CURRENT VERSION OF THE TECHNICAL STANDARD, NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL.

To Air Supply

PERMANENT SEEDING

- 1. REPLACE TOPSOIL TO A MINIMUM DEPTH OF 6 INCHES.
- 2. SEED 20 POUNDS OF PERENNIAL RYEGRASS PER ACRE AND 80 POUNDS PER ACRE OF KENTUCKY BLUEGRASS OR EQUIVALENT.
- 3. FERTILIZE WITH 600 POUNDS PER ACRE OF 10-10-10. LIME TO ACHIEVE A PH OF 6.0. IF HYDROSEEDER IS NOT USED, SEED AND FERTILIZER SHOULD BE LIGHTLY RAKED INTO SOIL.
- 4. MULCH WITH CLEAN (WEED FREE) STRAW.

TEMPORARY SEEDING

- IF SOILS ARE COMPACTED, SCARIFY UPPER TWO INCHES BY BACKBLADING WITH A DOZER, RAKING, OR DISKING.
- 2. IMMEDIATELY FERTILIZE WITH 300 LBS/ACRE OF 10-10-10. NOTE: NO FERTILIZER SHOULD BE USED AFTER OCTOBER 1ST IF THERE IS DANGER OF LEACHING INTO A WATER
- 3. IMMEDIATELY SEED WITH THE FOLLOWING MIX: 40 LBS/ACRE ANNUAL RYEGRASS 40 LBS/ACRE PERENNIAL RYEGRASS 40 LBS /ACRE CREEPING RED FESCUE

4 LBS/ACRE WHITE CLOVER (INOCULANT)

4. APPLY STRAW MULCH-STRAW MULCH IS NECESSARY TO HOLD IN MOISTURE, PROTECT SOIL FROM EROSION, HOLD SEED IN PLACE, AND KEEP SOIL TEMPERATURES MORE CONSTANT. 3 BALES PER 1000 SQ. FT.


1" PVC PIPING FIELD ADJUSTED TO HEIGHT 1/2" PVC Pipe ZIP TIES 1/4" THICK WALL IOS 500 INOCULANT PACKET 1/2" PIPING - 54x 1" ID TUBULAR MEDIA SECTION 1 US FILTER FLEX DISC FINE BUBBLE DIFFUSER SECTION 1 9IN. DIAMETER SECTION 2 — 1.5" DIA. BALAST COMPARTMENT PLUG CUSPATED WRAP 10 X 1.50" EQUALLY SPACED 1/2" PVC

VERTICAL CROSSECTION

SECTION 2

INOCULATOR DEVICE EXAMPLE

N.T.S.




GENERAL & UTILITY NOTES

- SAFE AND CONTINUOUS TRAFFIC AND INGRESS AND EGRESS FOR ADJACENT OWNER DRIVEWAYS, SERVICE AND PUBLIC ROADS SHALL
- BE MAINTAINED THROUGH THE PERIOD OF CONSTRUCTION.
- 2. ALL CONSTRUCTION RELATED TO THIS PROJECT SHALL BE IN CONFORMANCE WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL REQUIREMENTS.
- THE CONTRACTOR SHALL OBTAIN ALL APPROPRIATE PERMITS BEFORE BEGINNING ANY CONSTRUCTION.
- THE CONTRACTOR IS REQUIRED TO NOTIFY CENTRAL STAKEOUT,
- TELEPHONE NO. 1-800-962-7962 (811) FOR FIELD STAKEOUT OF UNDERGROUND UTILITIES BEFORE COMMENCING CONSTRUCTION.
- THE PROPOSED WATER APPURTENANCES SHALL CONFORM TO THE THE LOCAL WATER AUTHORITY'S STANDARDS.
- ALL WATER AND WASTEWATER APPURTENANCES SHALL CONFORM TO NYS HEALTH DEPARTMENT STANDARDS. THE CONTRACTOR SHALL PROVIDE FOR EROSION CONTROL BARRIERS
- DURING CONSTRUCTION AND FOR THE REMOVAL OF THE SAME AFTER GRADING AND SEEDING HAS BEEN ESTABLISHED.
- 8. THE CONTRACTOR SHALL BE REQUIRED TO CLEAN MUD AND DEBRIS FROM PUBLIC ROADS SERVICING THE CONSTRUCTION SITE DURING AND AFTER THE COMPLETION OF THE PROJECT.
- 9. THE CONTRACTOR SHALL NOTIFY AGENCIES PRIOR TO ANY EXCAVATING AND REQUEST SUCH UTILITY TO STAKE OUT WATER, GAS, ELECTRIC, AND/OR BURIED TELEPHONE LINES OR CABLES.
- ALL UTILITIES MUST BE BORED ACROSS THE COUNTY HIGHWAY. "OPEN CUT" OF THE HIGHWAY IS NOT PERMITTED.
- THE CONTRACTOR SHALL USE DUE CAUTION IN PROTECTING PROPERTY MARKERS AND ALL ELEVATION SURVEY STAKES.
- 12. THE ACCURACY OF EXISTING UTILITIES ARE NOT GUARANTEED. EXISTING UTILITIES SHOWN ON THE PLANS ARE A RESULT OF THE BEST INFORMATION THAT COULD BE OBTAINED FROM FIELD SURVEYS AND RECORD MAPS AND ARE FOR GENERAL INFORMATION ONLY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE LOCATION OF ALL PERTINENT UTILITIES BY FIELD INVESTIGATION. THE CONTRACTOR SHALL ALSO TAKE THE NECESSARY MEASURES TO PRESERVE AND PROTECT EXISTING UTILIITES.
- 13. ALL ELECTRICAL WORK SHALL BE PERFORMED IN CONFORMANCE WITH ALL NEC AND UL ELECTRICAL CODES
- 14. ALL WATERMAINS AND SERVICES SHALL HAVE A MINIMUM OF 5' (FEET)
 OF COVER FROM THE TOP OF THE MAIN TO THE FINISHED GRADE. THE
 CONTRACTOR SHALL CHECK ALL CUT STAKES BEFORE TRENCHING TO INSURE THAT ALL INSTALLED WATERMAINS WILL HAVE THE REQUIRED COVER.
- 15. THE CONTRACTOR SHALL COMPLY WITH THE NEW YORK STATE INDUSTRIAL CODE, RULE 23, SUBPART 23-4 "EXCAVATION OPERATIONS" AND ALL APPLICABLE O.S.H.A. REQUIREMENTS SO AS TO PROVIDE SAFE EXCAVATION PROCEDURES.
- 16. IT IS THE CONTRACTOR'S RESPONSIBILITY TO TEMPORARILY SUPPORT AND MAINTAIN OTHER UTILITIES AS REQUIRED.
- 17. ALL TRAFFIC MAINTENANCE INCLUDING SIGNS, BARRICADES, LIGHTS AND OTHER TRAFFIC CONTROL DEVICES SHALL BE IN CONFORMANCE WITH THE REQUIREMENTS OF THE NEW YORK STATE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
- 18. PROPOSED SLOPES SHALL NOT EXCEED 1 ON 3 EXCEPT WHERE NOTED.
- 19. THE CONTRACTOR SHALL READ AND BECOME COMPLETELY FAMILIAR WITH THE APPROVED DESIGN PLANS. SHOULD THE CONTRACTOR HAVE ANY QUESTIONS CONCERNING THE PROJECT DESIGN, CONTACT THE DESIGN ENGINEER PRIOR TO COMMENCING CONSTRUCTION.
- 20. MINIMUM SEPARATION BETWEEN WATERMAIN AND SEWER MAINS TO BE 18" VERTICALLY MEASURED FROM THE OUTSIDE OF THE PIPES AT THE POINT OF CROSSING. MINIMUM HORIZONTAL SEPARATION BETWEEN WATERMAINS AND SEWER MAINS/SERVICES TO BE 10' (FEET) MEASURED FROM THE OUTSIDE OF THE PIPES. IF A CROSSING SHOULD OCCUR ONE FULL LENGTH OF THE SEWER SHALL BE CENTERED UNDER OR OVER THE WATERMAIN SO THAT BOTH THE JOINTS WILL BE AS FAR FROM THE SEWER AS POSSIBLE. WHERE A WATERMAIN CROSSES UNDER A SEWER ADEQUATE STRUCTURAL SUPPORT (COMPACTED SELECT FILL) SHALL BE PROVIDED FOR THE SEWER TO PREVENT SETTLING.

CLWSC WASTEWATER SYSTEM NOTES

- THE CONTRACTOR SHALL CONTACT THE CANANDAIGUA LAKE WATERSHED INSPECTOR PRIOR TO COMMENCING CONSTRUCTION OF THE WASTEWATER SYSTEM.
- 2. A PERPETUAL MAINTENANCE AGREEMENT BETWEEN THE WASTEWATER INOCULATOR SYSTEM MANUFACTURER'S REPRESENTATIVE AND THE OWNER IS REQUIRED. A COPY OF THE AGREEMENT IS TO BE PROVIDED TO THE CANANDAIGUA LAKE WATERSHED INSPECTOR'S OFFICE.
- 3. THE WW SYSTEM MUST BE DESIGNED, SUPERVISED AND CERTIFIED BY A DESIGN PROFESSIONAL.
- 4. THE INOCULATOR TREATMENT UNIT WILL BE EQUIPPED WITH AN APPROPRIATE
- 5. THE SERVICE CONTRACT FOR THE INOCULATOR TREATMENT UNIT MUST PROVIDE FOR SEMI ANNUAL INSPECTIONS BY AN AUTHORIZED MANUFACTURER'S REPRESENTATIVE FOR AS LONG A TIME PERIOD AS THE UNIT IS IN USE. A COPY OF THE SERVICE CONTRACT AND REPORTS OF THE SEMI-ANNUAL INSPECTIONS SHALL BE PROVIDED TO THE OFFICE OF THE CANANDAIGUA LAKE WATERSHED INSPECTOR.
- 6. SUBMISSION OF A RECORD DRAWING OF THE COMPLETED SYSTEM INSTALLATION CERTIFIED BY THE DESIGN ENGINEER IS REQUIRED UPON COMPLETION OF THE



REVISIONS DESCRIPTION **PROFESSIONAL** TOWN REVIEW TOWN REVIEW 7171 VICTOR - PITTSFORD ROAD SEPT 2020

DETAIL SHEET SITE AND UTILITY PLAN - 4789 WEST LAKE ROAD TOWN OF CANANDAIGUA, ONTARIO COUNTY, NEW YORK STATE

AS SHOWN

ENGINEERING

HAROLD & TERRI BOBF 6 BRETTON WOODS DE ROCHESTER, NY 14618 PHONE:(585) 748-5464 TAX ACCOUNT NO. 140.14-1-16.100

NGINEER:

VICTOR, NEW YORK 14564 (585) 924-1860 EMAIL: PROENGINEER1@PRODIGY.NET DRAWN BY:

DRAWING NO .: 200901DT

COPYRIGHT 2020 BY PROFESSIONAL ENGINEERING SERVICES/GROUP

DRAWING ALTERATION

ALL HOUSE PLAN DRAWINGS PROVIDED BY ARCHITECTURAL INNOVATIONS