Maximum Building Coverage on Lot = 20%

Maximum Lot Coverage = 30%

No. 360598 0020 C Last Dated March 3, 1997.

Existing Lot Coverage Calculations: Sq.Ft ----house to be demo'd (-915sf) ..907.0 Garage... Driveways.. ---portion to be removed...... (-645sf) Deck... —---shed to be removed..... (-50sf) —---portion to be removed...... (-148sf) Walkway.. . 203.0

New house..


Total Coverage... Contours derived from NAVD88 Datum Total Site Area.. **Building Coverage**..(1,909sf)..... Flood Zones AE & X Per Community Panel Total Lot Coverage...


New Coverage.. .. 4,144.0 .12,598.0 New Bldg. Coverage. (2,539sf).... 20.00% (up 4.85% from existing) . 15.15%33.9%


	PROPOSED	REQUIRED
ZONING/ USE - PRINCIPAL	NEW HOUSE	RLD
FRONT SETBACK	41.33'	55. <i>0</i> '
SIDE SETBACK	So 10.2' exist. No 10.0' prop.	100'0
REAR SETBACK	existing 42.75	3 <i>Ø.</i> Ø'
BUILDING HEIGHT	25 <i>.00</i> '	25 <i>.</i> Ø'

ZONING BOARD OF APPEALS GRANTED AN AREA VARIANCE FOR FRONT YARD SETBACK, DATED JANUARY 19, 2021. REQUESTED 41.33ft FRONT SETBACK WHEN 55.00ft IS MIN: 13.67 FRONT SETBACK GRANTED

PLANNING BOARD CHAIRMAN	DATE
TOWN ENGINEER	DATE
WATER SUPERINTENDENT	DATE







SPI

TYPICAL SILT FENCE DETAIL SCALE: n.t.s.

LANDSCAPING, GRADING AN EROSION CONTROL

- 1. Topsoil shall be stripped from building excavation area and all areas to receive new pavement, including walks, and stockpile for use in new seeded and landscaped areas. Provide seeding of all stockpiled earth areas.
- 2. Prior to Construction, all erosion control measures in undisturbed area shall be placed as shown on the plans. Immediately following earth operations, remaining erosion control measures shall be installed.
- 3. All erosion control measures shall be maintained during the period of construction to the satisfaction of the Town of Irondequoit, and shall remain in place until so authorized by the local Zoning officer to proceed with their removal.
- 4. All disturbed areas to be topsoiled and seeded. Topsoil to be spread to a minimum depth of 6", and shall be of good quality and fine raked to elevations shown on the plan. All areas of topsoil spreading by the Contractor shall be seeded and mulched by the Contractor immediately after final grading.
- 5. All vegetation removed during clearing and grubbing shall be disposed of off site in a legal manner. All existing trees and vegetation shall be removed as necessary to complete the work unless specified to remain.

CONSTRUCTION SEQUENCE:

- 1. Install temporary erosion control measure including but not limited to: silt fence, stabilized entrances, etc.
- 2. The Contractor shall selectively remove vegetation and roots as required.
- 3. Place silt fence for stockpile area.
- 4. Strip topsoil.

CANANDAIGUA LAKE

- 5. Construct building and install utilities.
- 6. In the event there is a sediment dischare or failure, the Contractor or Owner shall be responsible for restoration.
- 7. Final grade, seed, and mulch disturbed areas as soon as

TO BE REMOVED.

MEAN HIGH WATER

MARCELLO & STACY

154.90

PROPERTY LINE @ MEAN HIGH WATER

N15° 49' 06"E

AREA = 0.289 ACRE 12,598 SQ FT

TO MEAN HIGH WATER LINE

NEW CANTILEVER—

FRAME- FIREPLACE

- LANDSCAPE BED @

WEST SIDE OF

EXISTING PATIO:

Spirea; Black Eyed

Susan's; Miniature

8. Install dry swale after areas contributing drainage

GENERAL NOTES

- 1. The Contractor shall verify the location and sizes and elevations of all existing utility mains and laterals and/or entrances. The Contractor shall be responsible for determining the exact location and depth of all utilities and structures within the path of or closely parallel to or under the proposed construction area. Notify Underground Facilities Protective Organization (UFPO) two days prior to any digging, drilling or blasting, at 1-800-962-7962, for a utility stake out.
- 2. The Contractor shall be responsible for all damages and repairs to all utilities, public and private roadways, sidewalks and structures, including signs, resulting from his work.
- 3. The roadway shall be kept free of debris during construction, and safe and continuous ingress and egress traffic shall be maintained throughout the period of construction. Contractor shall confine his work to areas within property lines.
- 4. Proper warning signs and barricades shall be in place prior to the commencement of construction. All excavations shall be properly backfilled or barricaded at the end of each working
- 5. The Contractor is responsible for safety control devises. Such devices (barricades, fencing, etc.) shall be implemented to minimize risk of injury to pedestrians and workers. Construction activity shall be conducted within compliance with OSHA guidelines.
- 6. Plans are graphic representations of work to be performed. These plans are intended to convey engineering information
- 7. Contractor to verify all property lines, locations, grades and inverts and notify Engineer of any discrepancies prior to the start of work
- 8. All specified materials are to be installed as per manufactures recommendations or industry standard.

Site Plan information as taken from an instrument survey file drawing provided (prepared and certified) by Venezia Land Surveyors and Civil Engineers - LS #050864, completed September 8, 2020.

Proposed house, addition detail updated by Hanlon Architects.

- DOWNSPOUTS TO

EACH CORNER

(general note #16)

55.0' reg'd

SPLASH BLOCKS @

41.33' prop.

DRIVE

DRIVE

FEMA/ Federal Law requires finish

13.67'

EXIST. TREE TO BE

REMOVED. (ash)

-LINE OF EROSION —

CONTROL (silt fence)

TEMP. STOCKPILE -

AREA.

floor elevation to be above 693.7':

Existing FF elev: 693.0

T.M.# 98.15-1-29.0

N/F LINDA E. WILLIAMS

LIBER 1434 PAGE 761

LINE OF EROSION —

CONTROL (silt fence)

T.M.# 98.15-1-32.0

N/F LESLIE FERRITER

LIBER 1442 PAGE 532

Proposed FF elev: 694.33


9. Engineer and Architect do not hold any liability for system failure. Any system modifications or deviations from the approved plans, NYS Building Codes, and/or local regulations required by site constraints, unforeseen conditions or covering authorities will be done at the risk of the client.

10.All construction shall comply with current NYS and local building codes as well as National Electric Code.

- 11. The Contractor shall verify the Building foundation "footprint" and location with the Architect prior to commencement of the work.
- 12. Water Service: To remain on site. Adjust as necessary.

13. Sanitary Lateral: To remain on site. - Adjust as necessary.

- 14. Gas and Telephone services to remain on site. Adjust as
- 15. Existing overhead Electric service to be removed. New underground service to be provided. Location to be determined per site conditions.
- 16.Storm Sewer shall remain- be modified per new footprint and driveway. Once existing conditions have been identified, modifications shall be documented for file record. Downspout shall be at each corner of house w/splash blocks in direction away from neighboring properties.
- 17. All General Contractors and Subcontractors shall visit the Site prior to submitting bids to familiarize themselves with existing conditions and to determine the exact scope of work
- 18. All utilities shall be underground- N/A no new utilities are scheduled.
- 19. No new site grading is scheduled or anticipated for the project. Intent for site and the new construction is to keep existing as much as possible, and for the new building to be over the footprint of the existing.
- 20. No phosphorous shall be used at planting time unless testing has be completed by a Horticultural Testing Lab. If test indicates a phosphorous deficiency, phosphorus shall be applied following NYS DEC regulations.
- 21. All exterior lighting shall be dark sky compliant and not directed onto the neighboring properties.



Centerline Gas line (exist) Water line (exist)

Sanitary line (exist) _____s___s____s

T.M.# 98.15-1-29.0

N/F LINDA E. WILLIAMS

LIBER_1434 PAGE 761

T.M.# 98.15-1-32.0

N/F LESUE FERRITER

LIBER 1442 PAGE 532

-EXISTING SHED TO BE REMOVED (50sf.)

10-6-20



SITE PLAN SKETCH SPI SCALE: 1"=20'-0"

SLAB: 692.

LINE OF SANITARY @

ROAD. LATERAL TO

APPROX. LOCATION OF

EXISTING GRAVEL DRIVE TO BE REMOVED (645sf +/-).

HOUSE SHALL BE

MANHOLE 'J'.

VERIFIED IN FIELD.



SIDE FACH TTISTI SANDY

4

 \mathfrak{A}

W

W

SITE PLAN SKETCH

DRAWING TITLE:

DATE:



PROJECT NO: 20-13

