

Luminaire Schedule				Lum. Lumens				Part Number			
Symbol	Qty	Label	Arrangement	LMF	22100	22100	22100	132	132	132	132
4M	5	4M	SINGLE	1.000	22100	22100	22100	132	132	132	132
4M-2(180)	2	4M-2(180)	2 @ 180°	1.000	22100	22100	22100	132	132	132	132

Calculation Summary: 1.00 LUF				Units				Avg/Min			
Label	Units	Avg	Min	Max	Min	Avg/Min	Max/Min	Units	Avg	Min	Max/Min
PAVED AREA	Fc	6.47	18.1	1.0	6.47	18.10	18.10				
SITE	Fc	1.05	18.2	0.0	N/A	N/A	N/A				

Fixture Mounting Height: 17' AFG (15' Pole + 2.0' Base)

Pole Schedule: (7) OSQ-SSP-4011-15-OT-BZ (15' x 4" x 11ga. STEEL SQUARE POLE, Tenon)

Proposed poles meet 120 MPH sustained winds.

Additional Equipment:

(9) OSQ-ML-5AA-BZ (Adjustable Arm Mount)

(5) PB-1A4 (Single Head Tenon)

(2) PB-4M (Double Head Tenon @ 180)

*** CUSTOMER TO VERIFY ORDERING INFORMATION AND CATALOGUE NUMBER PRIOR TO PLACING ORDER ***

OSQ Series

15'

2'-0"



Layout By:
LINDA SCHALLER
Date: 8/19/2022

Filename: POP-220818CANNVLSJR1

Project Name: POPEYES-3225 NY Route 364, 14424
Case #: 00510780
Footcandles calculated at grade

CREE LIGHTING
A COMPANY OF IDEAL INDUSTRIES, INC.
8201 Washington Ave. Racine, WI 53406 https://creelighting.com (800) 235-8800

