# ONE STAGE(PRELIMINARY/FINAL) SITE PLAN SET FOR

### SHEET INDEX:

**COVER SHEET** 

**EXISTING CONDITIONS PLAN** 

SITE CONSTRUCTION NOTES AND DETAILS SITE GRADING AND DRIVEWAY LAYOUT PLAN

## TICHENOR POINT DRIVE RECONFIGURATION

# 4351 TICHENOR POINT DRIVE TOWN OF CANANDAIGUA ONTARIO COUNTY -- STATE OF NEW YORK





AERIAL LOCUS NOT TO SCALE

#### ONE STAGE SITE PLAN APPROVAL

PLANNING BOARD CHAIRPERSON


TOWN HIGHWAY & WATER SUPERINTENDENT

TOWN ENGINEER


Sheet:

NO BUILDING PERMIT MAY BE ISSUED UNTIL FINAL SITE PLAN APPROVAL HAS BEEN GRANTED AND THE FINAL SITE PLAN SIGNED BY THE PLANNING BOARD CHAIRPERSON.

FOR PERMITTING ONLY



PER SECTION 7209 OF ARTICLE 145 OF THE NEW YORK STATE EDUCATION LAW IT IS A VIOLATION FOR ANY PERSON TO ALTER ANY DOCUMENT THAT BEARS THE SEAL OF A PROFESSIONAL ENGINEER, UNLESS THE PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. IF A DOCUMENT BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE DOCUMENT THEIR SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION.



Site Plan Drawings Prepared For:

Rocco A. Venezia, P.L.S.

## ABDB SILVER SPRINGS LLC

4351Tichenor Point Drive Town of Canandaigua State of New York County of Ontario

File# 21103 Scale: AS NOTED T.m. # 126.16-1-1.10 Date: 08/11/2021

**C-**0

#### GENERAL NOTES

UNLESS OTHERWISE NOTED.

1. PROPERTY LINE INFORMATION SHOWN ON THIS PLAN IS BASED ON AVAILABLE RECORD INFORMATION AND ON A FIELD INSTRUMENT SURVEY PERFORMED BY VENEZIA AND ASSOCIATES ON JUNE 8, 2021.

2. UTILITIES SHOWN ON THIS PLAN ARE APPROXIMATE. ACTUAL LOCATION SHALL BE FIELD VERIFIED PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL PROTECT AND MAINTAIN ALL EXISTING UTILITY SERVICES THROUGHOUT CONSTRUCTION. CONTACT U.F.P.O. AT 1-800-962-7962 AT LEAST 72 HOURS PRIOR TO CONSTRUCTION.

3. THIS UPLAND PORTION OF THE SITE DOES NOT FALL WITHIN ANY FEMA SPECIAL FLOOD HAZARD ZONES, THE LAKE FRONTAGE AND DRAINAGE AREA ALONG THE SOUTHERN PROPERTY LINE ARE LOCATED IN ZONE A, PER C.P. #3605980025C MAP REVISED MARCH 3, 1997.

4. NO CHANGES ARE TO BE MADE TO THIS DESIGN WITHOUT PRIOR APPROVAL OF THE DESIGN ENGINEER.

5. ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE MOST RECENT STANDARDS AND SPECIFICATIONS OF THE TOWN OF CANANDAIGUA AND THE APPROPRIATE WATER/SEWER AGENCIES,

6. THE CONTRACTOR SHALL LOCATE, MARK, SAFEGUARD AND PRESERVE ALL SURVEY CONTROL MONUMENTS AND RIGHT-OF-WAY MONUMENTS IN THE AREAS OF CONSTRUCTION.

7. ELEVATIONS REFERENCE NAVD88 DATUM.

#### SITE PREPARATION & EARTHWORK SEQUENCE

- 1. SILT FENCING, EROSION CONTROL MEASURES AND LIMITS OF WORK BOUNDARIES ARE TO BE PLACED PER PLAN. INSTALL CONSTRUCTION ENTRANCE. ESTABLISH STAGING AREAS AND SOIL STOCKPILE AREAS. [OCTOBER 2021]
- AREAS AND SOIL STOCKPILE AREAS. [OCTOBER 2021]

  2. ESTABLISH PROPOSED DRIVEWAY AREA. INSTALL TEMPORARY SEDIMENT BASIN.
- 3. REMOVE EXISTING TENNIS COURT AND GRADE, STABILIZE DRIVEWAY.
- 4. CONSTRUCT NEW DRIVEWAY TO BINDER COURSE.
- 5. REMOVE EROSION CONTROLS AND CEASE MONITORING ONLY AFTER APPROVAL HAS BEEN GRANTED BY THE TOWN OF CANANDAIGUA AND/OR THEIR PROJECT REPRESENTATIVE. [MAY 2022]
- ACTUAL ON-SITE CONDITIONS MAY PRECIPITATE A NEED TO REVISE THE PROJECTED SEQUENCING LISTED ABOVE.

#### TOWN OF CANANDAIGUA STANDARD NOTES

- 1. ALL IMPROVEMENTS SHALL BE IN ACCORDANCE WITH THE MOST RECENT STANDARDS AND SPECIFICATIONS OF THE TOWN OF CANANDAIGUA AND THE APPROPRIATE WATER / SEWER AGENCIES, UNLESS OTHERWISE NOTED.
- 2. A STORMWATER POLLUTION PREVENTION PLAN (SWPPP) IS REQUIRED TO CONFORM WITH THE LATEST NYSDEC GENERAL PERMIT AND TO THE TOWN REQUIREMENTS REGARDING MAINTENANCE AND CONTROL OF STORMWATER QUALITY AND QUANTITY.
- MAINTENANCE AND CONTROL OF STORMWATER QUALITY AND QUANTITY.

  3. ALL SWPPP'S ARE REQUIRED TO BE REVIEWED AND APPROVED BY THE TOWN CEO AND TOWN ENGINEER. THE TOWN MS4 SWPPP ACCEPTANCE FORM IS TO BE SIGNED AND INSERTED INTO THE PROJECT SWPPP PRIOR TO CONSTRUCTION.
- 4. THE OWNER IS RESPONSIBLE FOR IMPLEMENTING THE REQUIRED SWPPP, INCLUDING FILING OF THE "NOTICE OF INTENT" (NOI). A COPY OF THE NYSDEC ACKNOWLEDGEMENT LETTER IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE AND TOWN ENGINEER PRIOR TO CONSTRUCTION.

  5. A COPY OF THE PROJECT SWPPP IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE, TOWN ENGINEER AND A COPY IS TO REMAIN ON SITE DURING CONSTRUCTION AT ALL
- 5. A COPY OF THE PROJECT SWPPP IS TO BE PROVIDED TO THE TOWN DEVELOPMENT OFFICE, TOWN ENGINEER AND A COPY IS TO REMAIN ON SITE DURING CONSTRUCTION AT ALL TIMES IN A MARKED AND ACCESSIBLE LOCATION.

  6. ANY MODIFICATIONS OR DEVIATIONS FROM THE APPROVED PLANS, CONSTRUCTION SEQUENCE, AND/OR SWPPP INCLUDING IMPLEMENTATION OF EROSION CONTROL MEASURES AND
- STORMWATER MANAGEMENT AREAS SHALL BE APPROVED BY THE TOWN OF CANANDAIGUA AND DOCUMENTED WITHIN THE PROJECT SWPPP.

  7. THE OWNER IS REQUIRED TO PROVIDE DAILY ON—SITE OBSERVATION BY A LICENSED PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL (CPESC).
- ALL SWPPP INSPECTIONS ARE TO BE IN A FORM ACCEPTABLE BY THE TOWN OF CANANDAIGUA AND FORWARDED TO THE OWNER, THE TOWN CEO, TOWN ENGINEER, AND A COPY PLACED WITHIN THE ON—SITE PROJECT SWPPP.

  8. THE OWNER IS RESPONSIBLE FOR PROVIDING ON—SITE SWPPP INSPECTIONS BY A LICENSED PROFESSIONAL OR A CERTIFIED PROFESSIONAL IN EROSION AND SEDIMENT CONTROL
- (CPESC) DURING CONSTRUCTION ONCE PER WEEK (EVERY 7 DAYS) IF UNDER 5 ACRES OF DISTURBANCE AND TWICE PER WEEK (EVERY 7 DAYS) IF 5 ACRES OR MORE WITH RECEIPT OF A 5-ACRE WAIVER FROM THE TOWN OF CANANDAIGUA (MS4).

  9. DEVELOPMENT IN THE CANANDAIGUA LAKE WATERSHED DISTURBING MORE THAN 5 ACRES AT ONE TIME IS REQUIRED TO COORDINATE THE REGULAR SWPPP OBSERVATIONS
- REQUIRED BY THE LATEST GENERAL PERMIT WITH THE CANANDAIGUA LAKE WATERSHED INSPECTOR, THE WATERSHED PROGRAM MANAGER, AND THE TOWN CODE ENFORCEMENT OFFICER.
- 10. CONSTRUCTION SEQUENCE: ALL PLANS ARE TO BE PROVIDED WITH A DETAILED CONSTRUCTION SEQUENCE. THE CONTRACTOR SHALL COMPLETE CONSTRUCTION AND INSTALL EROSION CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED CONSTRUCTION SEQUENCE UNLESS SPECIFIED OTHERWISE ON THE APPROVED DESIGN PLANS OR AT THE PRE-CONSTRUCTION MEETING.
- 11. DUST SHALL CONTROL DURING CONSTRUCTION BY THE CONTRACTOR TO MINIMIZE EFFECT ON THE ADJACENT PROPERTIES. THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL MEASURES AS NEEDED AND/OR AS DIRECTED BY THE TOWN OF CANANDAIGUA.
- 12. THE OWNERS CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT, MAINTENANCE, CLEANING, REPAIR, AND REPLACEMENT OF EROSION CONTROL MEASURES DURING SITE CONSTRUCTION AND UNTIL THE SITE IS FULLY STABILIZED, INSPECTED BY THE TOWN OF CANANDAIGUA, AND ISSUANCE OF THE NOTICE OF TERMINATION (NOT) HAS BEEN
- 13. ROOF LEADERS SHOULD BE CONNECTED TO STORM SEWERS WHERE POSSIBLE UNLESS OTHERWISE SPECIFIED ON THE APPROVED PLANS AND WITHIN THE PROJECT SWPPP.

  14. NO SITE PREPARATION SHALL COMMENCE UNTIL A VISUAL INSPECTION BY THE TOWN OF CANANDAIGUA CONFIRMS THE INSTALLATION OF PERIMETER SEDIMENT CONTROLS AND THE
- STABILIZED CONSTRUCTION ENTRANCE.

  15. UPON COMPLETION OF CONSTRUCTION AND ESTABLISHMENT OF VEGETATION, THE STORMWATER MANAGEMENT FACILITY SHALL BE CLEANED OF ACCUMULATED SILT.

  16. ALL SITE STABILIZATION IS TO BE IN ACCORDANCE WITH THE LATEST VERSIONS OF THE NYSDEC STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL AND THE
- 16. ALL SITE STABILIZATION IS TO BE IN ACCORDANCE WITH THE LATEST VERSIONS OF THE NYSDEC STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL AND THE NYSDEC GENERAL PERMIT REQUIREMENTS (WHERE APPLICABLE).

  17. ADDITIONAL TEMPORARY AND PERMANENT SEEDING AND SITE STABILIZATION REQUIREMENTS:
- A. ALL DISTURBED AREAS INCLUDING TOPSOIL STOCKPILES AND STORMWATER MANAGEMENT FACILITIES ARE TO BE STABILIZED WITHIN SEVEN (7) DAYS AFTER COMPLETION.
  B. TEMPORARY SEEDING OF DISTURBED AREAS SHALL BE PROVIDED AS FOLLOWS:

THE SURFACE TWO INCHES OF SOIL SHOULD BE LOOSENED BY DISKING RAKING OR BACK—BLADING WITH A BULLDOZER

FERTILIZE WITH 300 LBS PER ACRE OR 7 LBS PER 1000 SQUARE FEET

NO PHOSPHORUS SHALL BE USED UNLESS SOIL TESTING HAS BEEN COMPLETED AND TESTED BY HORTICULTURE TESTING LAB AND THE SOIL TESTS SPECIFICALLY INDICATE A PHOSPHORUS DEFICIENCY THAT IS HARMFUL OR WILL PREVENT NEW LAWNS AND PLANTINGS FROM ESTABLISHING PROPERLY.

IF SOIL TESTS INDICATE A PHOSPHORUS DEFICIENCY THAT WILL IMPACT PLANT AND LAWN ESTABLISHMENT, PHOSPHORUS SHALL BE APPLIED AT THE MINIMUM RECOMMENDED LEVEL PRESCRIBED IN THE SOIL TEST FOLLOWING ALL NYSDEC REGULATIONS.

## SPRING/SUMMER/EARLY FALL LBS/ACRE LBS/1,000 SQ. ACRE ANNUAL RYE GRASS 30 0.7

ANNUAL RYE GRASS 30 0.7
PERENNIAL RYEGRASS 30 0.7
LATE FALL/EARLY WINTER
CEREAL RYE 100 2.5

SEED SHOULD HAVE A GERMINATION RATE OF AT LEAST 85% AND MINIMAL INERT MATERIAL.

RECOMMENDED LEVEL PRESCRIBED IN THE SOIL TEST FOLLOWING ALL NYSDEC REGULATIONS.

C. DISTURBED AREAS SHALL BE STABILIZED USING PERMANENT LAWN SEED MIX UPON COMPLETION OF GRADING AND CONSTRUCTION:

LBS/ACRE LBS/1.000 SQ. ACRE
BIRDSFOOT TREFOIL OR COMMON WHITE CLOVER 8 OR 8
TALL FESCUE 20 0.45
REDTOP OR RYEGRASS (PERENNIAL) 2 OR 5

LBS/ACRE LBS/1.000 SQ. ACRE
0.20 OR 0.20
0.45
0.05 OR 0.10

SEEDING RATE 6 LBS PER 1000 SQUARE FEET

• THE FOLLOWING SEED MIX SHALL BE USED:

SEEDING RATE 6 LBS PER 1000 SQUARE FEET
 MULCH: STRAW OR WOOD FIBER MULCH USED WITH HYDROSEEDING METHOD AT 2 TONS PER ACRE WITH TACKIFIER.
 FOR FALL OR EARLY WINTER, SEED WITH CERTIFIED "AROOSTOCK" WINTER RYE (CEREAL RYE) AT 100 LBS PER ACRE.


FOR FALL OR EARLY WINTER, SEED WITH CERTIFIED AROUSTOCK WINTER RTE (CEREAL RTE) AT 100 LBS PER ACRE.
 PERMANENT STABILIZATION FOR STEEP SLOPES GREATER THAN 3:1 SHALL INCLUDE JUTE MESH BLANKET AND CROWN VETCH SEED WITH PERENNIAL RYEGRASS.
 NO PHOSPHORUS SHALL BE USED UNLESS SOIL TESTING HAS BEEN COMPLETED AND TESTED BY HORTICULTURE TESTING LAB AND THE SOIL TESTS SPECIFICALLY INDICATE A PHOSPHORUS DEFICIENCY THAT IS HARMFUL OR WILL PREVENT NEW LAWNS AND PLANTINGS FROM ESTABLISHING PROPERLY.
 IF SOIL TESTS INDICATE A PHOSPHORUS DEFICIENCY THAT WILL IMPACT PLANT AND LAWN ESTABLISHMENT, PHOSPHORUS SHALL BE APPLIED AT THE MINIMUM

- 18. THE CONTRACTOR SHALL LOCATE, MARK, SAFEGUARD, AND PRESERVE ALL SURVEY CONTROL MONUMENTS AND RIGHT-OF-WAY MONUMENTS IN THE AREAS OF CONSTRUCTION.


  19. EXISTING UNDERGROUND UTILITIES SHOWN HEREIN WERE PLOTTED FROM FIELD LOCATIONS AND/OR UTILITY COMPANY RECORD PLANS. PRIOR TO ANY CONSTRUCTION THE CONTRACTOR SHALL CALL THE DIG SAFELY NEW YORK UFPO HOTLINE AT 1-800-962-7962 FOR STAKEOUT OF EXISTING UTILITIES. THE CONTRACTOR SHALL DETERMINE EXACT LOCATION AND ELEVATION OF UNDERGROUND UTILITIES BEFORE COMMENCING CONSTRUCTION. CONTRACTOR SHALL MAKE EXPLORATION EXCAVATIONS TO LOCATE EXISTING UNDERGROUND FACILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS AS REQUIRED TO MEET THE EXISTING CONDITIONS.
- 20. THE HOMEBUILDER WILL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING INDIVIDUAL LOT EROSION AND SEDIMENT CONTROL MEASURES DURING HOUSE CONSTRUCTION. MEASURES
  TO BE MAINTAINED UNTIL FINAL LOT LAWN GRADING AND SITE IS FULLY STABILIZED AND INSPECTED BY THE TOWN OF CANANDAIGUA.
  21. ANY ADDITIONAL OR EROSION OR SEDIMENT CONTROL MEASURES DEEMED NECESSARY BY THE TOWN OF CANANDAIGUA OR A REPRESENTATIVE THEREOF SHALL BE PROVIDED BY
- 21. ANY ADDITIONAL OR EROSION OR SEDIMENT CONTROL MEASURES DEEMED NECESSARY BY THE TOWN OF CANANDAIGUA OR A REPRESENTATIVE THEREOF SHALL BE PROVIDED BY THE OWNER AND INSTALLED BY THE CONTRACTOR.

  22. SEDIMENT CONTROL MEASURES ARE TO BE ESTABLISHED PRIOR TO COMMENCING EARTHWORK. SEDIMENT CONTROL MEASURES ARE TO BE MAINTAINED BY THE CONTRACTOR UNTIL UPSTREAM GROUND COVER HAS BEEN ESTABLISHED AND REMOVAL IS APPROVED BY THE TOWN OF CANANDAIGUA.
- 23. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING, REPLACING, AND SUBSEQUENTLY REMOVING TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES.

  24. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING ADJOINING PROPERTIES, ROADWAYS, DRAINAGE WAYS, AND SINKS OF SILT ACCUMULATION AS NEEDED AND AS DETERMINED/REQUESTED BY THE TOWN OF CANANDAIGUA.
- 25. ANY FINAL GRADE DEVIATIONS OF HOUSE PAD ELEVATIONS MORE THAN 12 INCHES SHALL BE APPROVED BY THE PLANNING BOARD.



BITUMINOUS CONCRETE PAVEMENT
NOT TO SCALE



SILT FENCE DETAIL NOT TO SCALE

FILTER FENCE FABRIC SHALL BE OF

NYLON, POLYESTER, PROPYLENE, OR ETHYLENE YARN WITH EXTRA STRENGTH

- 50LB/LIN, IN,(MIN), WITH A FLOW

GAL./SQFT/MINUTE. FABRIC SHOULD

CONTAIN UV RAY INHIBITORS AND

RATE OF AT LEAST 0.3

**ZONING CHART** 

TOWN OF CANANDAIGUA

REQUIRED

20,000 SF

125'

60'

100'

25 FT

15%

25%

.. 18,319

.. 3,670

. 6,615

6,900

440

24,700 SF

EXISTING

167,183 SF

304.75

368.2'(HSE)

345.3'(SHED)

65.0'(HSE)

49.6'(SHED)

93.1

65.0'(HSE)

49.6'(SHED)

2.2%

11.0%

PROPOSED

167,183 SF

304.75

368.2'(HSE)

65.0'(HSE)

49.6'(SHED)

93.1

65.0'(HSE)

49.6'(SHED)

2.2%

8.4%

3,670

. 9,260

440

14,064

167,183

Proposed Lot Coverage Calculations:

Building Coverage...... 3,670

Building Coverage.....2.2%

Total Lot Coverage.....8.4%

Asphalt Driveway...

Total Coverage.....

Total Site Area.....

Buildings

Walkways ...

Stream Wall.

Tennis Court....

345.3'(SHED)

ZONING DISTRICT: RESIDENTIAL LAKE DISTRICT (RLD)

MIN LOT AREA

(AREA TO ROW)

MIN LOT WIDTH

MIN FRONT YARD

MIN SIDE YARD

SETBACK

MIN REAR YARD

SETBACK

MIN SETBACK TO

MAX BUILDING HEIGHT

MAX BUILDING

COVERAGE

MAX LOT COVERAGE

SITE DISTURBANCE

Buildings

Tennis Court..

Walkways ...

Stream Wall.

Existing Lot Coverage Calculations:

Asphalt Driveway..

Building Coverage...... 3,670

Total Site Area..... 167,183

Building Coverage.....2.2%

Total Lot Coverage.....11.0%

Total Coverage.....

STREAM

SETBACK

ONE STAGE SITE PLAN APPROVAL

PLANNING BOARD CHAIRPERSON DATE

TOWN HIGHWAY & WATER SUPERINTENDENT

TOWN ENGINEER

NOTE:
NO BUILDING PERMIT MAY BE ISSUED UNTIL FINAL SITE PLAN APPROVAL
HAS BEEN GRANTED AND THE FINAL SITE PLAN SIGNED BY THE
PLANNING BOARD CHAIRPERSON.

FOR PERMITTING ONLY



VENEZIA AND ASSOCIATES
5120 LAURA LANE, CANANDAIGUA NY
rocco@veneziasurvey.com
585.396.3267

JOYCE CONSULTING GROUP, PC
100 WYMAN ROAD, BRAINTREE MA
www.joyccg.com
781.817.6120

PER SECTION 7209 OF ARTICLE 145 OF THE NEW YORK STATE EDUCATION LAW IT IS A VIOLATION FOR ANY PERSON TO ALTER ANY DOCUMENT THAT BEARS THE SEAL OF A PROFESSIONAL ENGINEER, UNLESS THE PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. IF A DOCUMENT BEARING THE SEAL OF AN ENGINEER IS ALTERED, THE ALTERING ENGINEER SHALL AFFIX TO THE DOCUMENT THEIR SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY THEIR SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A

SPECIFIC DESCRIPTION OF THE ALTERATION.

rofessional Engineer		Revisions	
TEOFNEW	NO.	Date	Description
LEIN VENEZIA O	1	8/20/2021	Town Development Office Comments
TO Z P			
CI CANA X			
086764			
POFESSIONALE			

Rocco A. Venezia, P.L.S.

EVI

Site Plan Prepared For:

Drawing Title:

POSTS SHALL BE 4" MIN. DIA. PINE LOCATED DOWNSLOPE OF

SLOPE

COMPACTED FILL OVER TOE OF

FABRIC TO HELP SUPPORT FENCE.

SITE CONSTRUCTION NOTES AND DETAILS

ABDB SILVER SPRINGS LLC

4351Tichenor Point Drive
Town of Canandaigua

County of Ontario State of New York

File# 21103
Scale: AS NOTED
T.M. # 98.13-1-16.11
Date: 08/11/2021
Sheet:

DATE

